

粉嶺公立學校

新界 粉嶺 粉嶺村

FANLING PUBLIC SCHOOL

FANLING VILLAGE FANLING N.T.

2670 2297 2673 6429

傳真: 2668 5371

學校檔案: <u>2021-2022WQ03</u>

邀請書面報價 承投提供校園數碼閉路電視(CCTV)錄影系統及安裝服務

敬啟者:

現誠邀 貴公司承投提供隨附的報價附表所列的服務。倘 貴公司不擬提供部份服務/物品內容,請於投標附表上清楚註明。

書面報價必須填妥<u>一式兩份</u>,置於密封信封內,信封面清楚註明:「<u>承投提供校園數碼閉路電視(CCTV)錄影系統及安裝服務</u>」,但承投商<u>不可</u>在報價書封面上顯示該公司的身份。報價書須於 2022 年 7 月 19 日(星期二)中午 12 時正前交往粉嶺 粉嶺村 651 號 粉嶺公立學校。逾期的報價,概不受理。

貴公司的報價書有效期為 90 天,由上述截標日期起計。如在該 90 天內仍未接獲訂單,則是 次報價可視作落選論。另外亦請注意, 貴公司必須填妥報價表格及附表,否則標書概不受理。

倘 貴公司未能或不擬報價,亦請盡快把報價表格寄回上述地址,並列明不擬報價的原因。 學校招標承投所需的服務/物品時,會以「整批」形式考慮接受供應商的報價,及以提供項目的 價目(60%)、售後服務(20%)及商譽(20%)為評選準則。

根據《防止賄賂條例》,「競投人及其僱員和代理人不得向學校僱員、法團校董會成員,或負責考慮與本招標有關事宜的委員會的任何家長或學生代表提供利益(香港法例第 201 章《防止賄賂條例》所界定的「利益」)。假如競投人、其僱員代理人向有關人士提供任何利益,根據《防止賄賂條例》可構成罪行,並可導致合約無效。學校亦可取消批出的合約,而競投人須為學校所蒙受的任何損失或損害負責。」

如有查詢,請於 2022 年 6 月 24 日至 7 月 15 日期間致電 $\underline{2670}$ $\underline{2297}$ 與古兆然主任聯絡。專此奉達,敬祝台安!

此致 貴公司

粉嶺公立學校校長



余美賢 謹啟

粉嶺公立學校

承投提供校園數碼閉路電視(CCTV)錄影系統及安裝服務

書面報價表格

(須填寫一式兩份)

學校名稱及地址: 粉嶺公立學校	新界粉嶺 粉嶺村 651 號	
學校檔案 <u>: 2021-2022WQ</u>)3	
截標日期/時間 : 2022 年 7 月 19 日	<u> 3 (星期二) 中午 12 時正</u>	
附表上所列的全部或部分項目。而是 署人知悉,所有未經特別註明的項 日期起計 90 天內仍屬有效,校方不	格(其他費用全免),以及校方提供的要求,提 完成服務及/或服務提供日期將於正式合約」 目,均須按照該細則的規定提供服務;報價 一定採納索價最低的報價書,並有權在報價。下方簽署人亦保證其公司的商業登記及僱	上註明。下方簽 賈書由上述截止 賈書有效期內,
7400 1 100	再確定本機構的報價書有效期由 <u>2022年7</u> 買書的有效期一經再行確定,其公司就該事	
日期: 年 月 _	日	
姓名:		
簽署:	. 職銜:	_(請註明職位)
	(公司名 址為	
電話號碼:		
傳真號碼:		
電子郵件:		

承投提供校園數碼閉路電視(CCTV)錄影系統及安裝服務(2021-2022WQ03)

書面報價書附表

(須填寫一式兩份)

第(4)-(7)項 須由供應商填寫

(1)	(2)	(3)	(4)
Item No.	Description/Specification	<u>Qty</u>	Unit Rate / Amount (HK\$)
	Supply and Install color CCTV System		
1	32 Channel 8MP Face Recognition RAID Network Video Recorder (*Please Listed the brand,	1 PC	¢
<u>1.</u>	model and place of production)	<u>11C</u>	Ψ
	- Support 32 channel 8MP & 4K recording at 25FPS / 30FPS, with 16T HDD (8TB x 2nos)		
	- Multi-HDD cycle recording		
	- Support 16Ch Simultaneous Playback		
	- 4K output, True High Resolution Display		
	- Dual stream recording		Brand:
	- Map of Face Trace - Resolution: 600 x 300 ~ 3840 x 2160		
	- Intelligent Analytics - Support object abandoned/missing detection, region entrance/exiting/intrusion detection		
	(human/vehicle classification) line crossing detection (human/vehicle classification), video tempering detection, scene change detection, face detection, face capture, crowded density detection, heat map, human/vehicle counting,		Model:
	human tracking		Model:
	- Set up each channel's record resolution and frame rate, also motion detection zone and sensitivity freely		
	- Scheduled record, Continuous record and motion detection		
	- Intelligent searching for historical DVR files		Place of production:
	- Remote monitor, remote playback, remote recording and remote backup by browser or DVP		
	- Support local and remote PTZ control		
	- Back up in EXE format which can play the recording files without any other player.		
	- HDMI x 2: 4K x 2K / 1920 x 1080 / 1280 x 1024, 1920 x 1080 / 1280 x 1024		
	- SATA x 8, e-SATA x 2 Supported, max 8TB per HDD		
	- Support Disk Array: RAID 0, 1, 5, 6, 10		
	- Support Face Picture Search: Search by picture is supported		
	- Support Database Management: Add, modify, delete and search face pictures		
	- Support disk group configuration and management and each camera can be added into different		
	disk groups with different storage capacity		
	- Remote zoom in / out of camera with motoring lens		

	- Must be connected to the existing CCTV system CMS software (Must be the following brands: VidoNet, Sony, Axis)		
<u>2.</u>	4M Starvis IR Water-proof Bullet IP Camera (*Please Listed the brand, model and place of production) - 1/2.7" CMOS Sensor, 4M pixels - 4MP (2560 × 1440) H.265 full real time coding - Color:.009 Lux @F1.2, AGC ON; 0 Lux (IR LED ON) - 2.8mm @F2.0, Angle of View: 112° - Weather-proof IP67 - Built-in efficient IR LEDS, IR distance up to 20~35m IR-CUT auto switch - WDR; - ONVIF Profile S - MPEG-4/H.264/H.265 - DC 12V / PoE - Built-in POE - Dimensions (mm): recommend not over (167.5mm x 74.5mm) - Must be connected to the existing CCTV system CMS software (Must be the following brands: VidoNet, Sony, Axis)	16 PCS	\$x 16pcs = \$ Brand: Model: Place of production:
<u>3.</u>	Managed 24-Port Gigabit PoE+ (410W) Switch with 4 SFP+ Fiber Ports (*Please Listed the brand, model and place of production) - Must be connected to the existing CCTV system CMS software (Must be the following brands: Linksys, VidoNet, H3C, Cisco)	<u>2 PCS</u>	\$ x 2pcs = \$ Brand: Model: Place of production:

<u>4.</u>	32" LED Monitor with Wall mount Bracket (*Please Listed the brand, model and place of production) - with HDMI input x 2 / VGA / AV input - (Must be the following brands: LG, Sony, Samsung)	<u>1 PC</u>	\$Brand: Model: Place of production:
<u>5.</u>	"Eight" 12U Server Rack - W600 x D600 Wallmount Cabinets - Fixed Shelf x 1, AC Fan x 2	<u>1 PC</u>	\$
<u>6.</u>	 Installation fee for CCTV System for whole school which is including all labour to install, material, parts, PVC conduit, Underground conduit work ,multi core Power Cable, signal cable, Cat5 & Cat6E cable, wire, accessories, engineer to install, config, Wall cutting & make good, testing, commissioning and full set training and one-year warranty for equipments and installation. (The Cat5 & Cat6E color of the wire is selected by the customer & Before the project starts, the supplier needs to provide the CCTV circuit diagram & schedule) 	<u>1 JOB</u>	\$
<u>7.</u>	 Training: provide training courses for the school's technical and operational staff to acquire full knowledge and appreciation of all aspects of the day-to-day operation, routine and preventive maintenance, fault diagnosis and rectification of the system. 	<u>1 JOB</u>	(INCLUDED)
<u>1-7.</u>	(5) Total Amount (H	<u>(K\$)</u>	\$

(6) The Contractor must be capable of fulfilling the requirements set out below:			(8) be capable of fulfilling the terms				
A. Insurance: The bidder must, on its own, purchase contractor all risk and third-party insurance (not less than HKD10 million) for this project.		Yes	/	No)		
B. Cleaning & Clearing: After the works have been completed, all components and the locations used by the works must be thoroughly cleaned and all construction waste is properly disposed in according to the Construction Waste Disposal Ordinance and construction waste disposal charging should be included.			/	No)		
C. Defects Liability and Warranty Period: 1. Defects liability period (1 years) which should include the following services: - Provide full guarantee of equipment and installation - Ensure the stability of the system connection(including but not less than cables, wires or other related accessories, etc.) - Provide professional logistic support (phone and email). - Provide free emergency on-site support and repair service. - Provide free replacement for the damaged components and accessories with repair services. - School have the right not to pay the retention amount and extend the DLP period if there is not any replacement for the damaged components or the supplier does not finish the defect work during the DLP period. 2. Warranty period (1 years after DLP period) which should include the following services: - Provide grantee of installation and ensure the stability of system connection. - Provide professional logistic support (phone and email). - Provide free emergency on-site support and repair service - Provide quotation for the damaged components, accessories and spare parts		Yes	/	No)		
D. Payment term: 1. Completion of the project upon goods satisfaction by school: 90% 2. Retention (finish of Defects Liability Period (DLP): 10%		Yes	/	No)		
E. Security Company Licence: The security company and Technical staff who undertake our school must hold the following security company licenses: Company Security Licence: I & III ; Technical staff: Security work category codes: D		Yes	/	No)		
(7) Please provide a list of service school units that your company has supplied and installed CCTV System over the past three years.		Atta Yes		ed: No)		
公司/本人明白,如收到學校訂單後未能供應報價書上所列物料或服務,本公司/本人須負責賠償學校從另處採購上述物料或 公司名稱: 地址:	或服:	務的差					
				`			
#絡人姓名:				/			

承投提供校園數碼閉路電視(CCTV)錄影系統及安裝服務(2021-2022WQ03)

参考附件:Floor plan - 新增的CCTV安裝位置 (見紅色圖示)

